BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Dasarahalli Division

D.T.S

NAME OF WORK:- COMMUNITY PROPERTY AND IMPROVEMENTS TO PARK IN WARD NO 13

S No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
1	KSRB 7.14 : Providing, fabricating, assembling and fixing in position aluminium partitions using sections in combination of plain, single grove and double grove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single grove section 2.541kg/m. and double grovesection 2.683 kg/m and bottom 46 kg/m; aluminium louvres of size 77.6mmx27.6mm 1.7mm. thick section weight 0.483kg/m; bottom portions provided with 12mm. thick prelaminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and rivetted to the frames, the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns or masonry on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistling and making good with cement mortar to match the surface, providing and fixing bottom panel filled with the materials to a height of 0.9m. from floor level; and 5.5mm. thick plain glass for middle portion viz., 0.9m. to 2.13 m. and top panel with lower sections, the glass and panels fitted with glazing clips of 19mmx17.3mm. with thickness of 0.9mm, weight 0.124kg/m; aluminium	Sqm	38.19	5178.60	Rupees Five Thousand One Hundred SeventyEight Paise Sixty Only

EXE[illegible] ...INEER
Bruhat Ba[illegible] palike
Dasarahalli Divi[illegible] ...560 057

S No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
2	KSRB 7.17 : Providing, fabricating, assembling and fixing in position aluminium doors using following aluminium mat finish or glossy finish, outer frame plain section 101.6x44.45mm thickness 3.18mm, section weight 2.404 kg/m, door shutters vertical section 44.62x44.45mm thickness 3.18mm, section weight 1.505kg/m, top section 47.62x44.45mm thickness 3.00mm, section weight 1.426kg/m bottom section 114.3x44.45 thickness 3.18mm, section weight 2.646kg/m, door central section 49.91x44.45mm thickness 3.00mm, section weight 1.495 kg/m glazing clips 19x17.3x11mm thickness 0.9mm section weight 0.124kg/m; aluminium sections cut to length joint metred cornersgrinded, the shutters pivoted opening arrangement with heavy duty aluminium alloy automatic door closures floor mounted, providing and fixing standard approved accessories, such as aluminium handle for full width or length, tower bolts, lock, pivots: P.V.C. or rubber gasket with 5.5m. thick plain glass for top and bottom panel; aluminium sections treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherance of mortars or any other sticky materials; the assembled frame fitted with the corner angles, strips and fitted with screws, rawl plugs or teakwood gutties to R.C.C. columns or masonry on sides. beams and flooring in bottom. including cutting, chistling and making good with cement	Sqm	5.67	6717.60	Rupees Six Thousand Seven Hundred Seventeen Paise Sixty Only
3	Dismantling weather proof course and removing and conveying the debris to a distance upto 200m..(PWD SR 2018-19 P.No: 269, I.No.: 37.44)	Cum	43.70	799.20	Rupees Seven Hundred NinetyNine Paise Twenty Only
4	For roof slab & terraces Providing & applying water proofing to roof slab, terraces, landscape area, podium etc., using modified polyurethane cures (conforming to ASTM C836-84) to give a tough elastomeric waterproof membrane on the surface. The surface shall be cleaned free from dust and other particle before usage. standards & methodology : This compound has a medium viscosity grade with 620% of elongation and shall be done either by roller application/brush application/ spray.. This will be applied for a thickness of 1.3mm first layer 0.5mm & 2nd layer 0.8mm. After applying the 2nd layer sand sprinkle shall be done to provide mechanical key. (PWD SR 2018-19 P.No: 275, I.No.: 38.2)	Cum	43.70	675.00	Rupees Six Hundred SeventyFive Only

EXECUTIVE ENGINEER
Bruhat [illegible] Palike
Dasarahalli Division, Bangalore - 560 057.

S No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
5	KSRB 24-36 : Removing the glazed tiles in patches in area exceeding 10 tiles and not exceeding 5 sqm including removing old tiles preparing surfaces and laying or setting new or old tiles complete including cost of materials, (excluding cost of tiles) labour, complete as per specifications. Specification No.KBS (PWD SR 2018-19 P.No: 133, I.No.: 16.31)	Sqm	41.85		
6	Providing and fixing Special make glazed Vitrified tiles (Granomite finish) of approved make, quality and colour of size 600x600x10mm thick fixed on existing flooring with a special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete. (PWD SR 2018-19 P.No: 109, I.No.: 14.45)	Sqm	41.85		
7	Providing and fixing storage unit of 0.75m width made out of 19mm thick commercial ply vertical support finished in approved 1.5mm laminate with 12mm thick ply packing internally finished with enamel paint of approved colour and shade shelves shall be formed out of 19mm ply finished with enamel paint of approved shade and colour and 19mm thick shutters formed out of 19mm thick ply finished with 1.5mm thick laminate of approved shade and colour etc., complete the rate includes cost of all materials, labour charges, complete as per specification. (PWD SR 2018-19 P.No: 324, I.No.: 39.4)	Sqm	11.34		
	KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.(PW,P& IWTD SR 2018-19, Pg No 119, Item No. 15.49.1)	Sqm	843.33		

Number of corrections

DTS Approved

Executive Engineer
Dasarahalli Division

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara P
Dasarahalli Division, Bangalore - 56